

Metropolitan Regional Roads Group Program - 2025/2026 - Summary of Projects

| Site | Location | Recommended treatment | MRRG contribution 2/3 | City contribution 1/3 | Total project cost excluding line marking |
|---------------|--|--|-----------------------|-----------------------|---|
| 1 | Hale Road, FF, (1020006) Road Rehabilitation, Reynolds Road to Dawson Avenue, SLK 2.03 to 3.00 | Mill 40mm Deep, Fill 14 DGA_CRM 75, 40mm Thick | \$314,091 | \$157,045 | \$471,136 |
| 2 | Hale Road, FF, (1020006) Road Rehabilitation, Stringybark Drive to Berkshire Road, SLK 4.31 to 4.49 | Mill 40mm Deep, Fill 14 DGA_CRM 75, 40mm Thick | \$82,643 | \$41,322 | \$123,965 |
| 3 | Lesmurdie Road, LM, (1020008) Road Rehabilitation, Glyde Road to Grove Road, SLK 1.50 to 2.11 | Mill 40mm Deep, Fill 14 DGA_CRM 75, 40mm Thick | \$208,086 | \$104,043 | \$312,129 |
| 4 | Lesmurdie Road, LM, (1020008) Road Rehabilitation, Godwin Street to Brady Road, SLK 2.89 to 3.35 | Mill 40mm Deep Fill, 14 DGA_CRM 75, 40mm Thick | \$141,387 | \$70,693 | \$212,080 |
| 5 | Maida Vale Road, HW, (1020009) Road Rehabilitation, Roe Hwy Off Ramp to West of Plover Road, SLK 1.14 - 1.31 | Mill 30mm Deep, Fill 10 DGA_CRM 75, 30mm Thick | \$53,908 | \$26,954 | \$80,862 |
| 6 | Welshpool Road East, WG, (1020002) Road Rehabilitation, Schofield Road to Gavour Road, SLK 2.10 to 2.84 | Mill 40mm Deep Fill 14 DGA_CRM 75, 40mm Thick | \$175,576 | \$87,788 | \$263,363 |
| Totals | | | \$975,690 | \$487,845 | \$1,463,536 |