

## Metropolitan Regional Roads Group Program – 2026-2027 - Summary of Projects

SN	Name of road	Project Name	Proposed treatment	MRRG (2/3)	City's Contribution (1/3)	Total cost
1	Welshpool Road East	Welshpool Road East, LM, (1020002) Road Rehabilitation, Lesmurdie Road to Silverdale Road, SLK 4.75 to 5.34	Mill 40mm Deep, Fill 14 DGA_CRM 75, 40mm Thick	\$322,343.21	\$161,171.61	\$483,515
2	Ridge Hill Road	Ridge Hill Road, MV, (1020023) Road Rehabilitation, Midland Road to Bridle Drive, SLK 0.00 to 0.37	Mill 55mm Deep, Base Layer 25mm SMA, Wear Layer 30mm Thick DGA	\$105,549.44	\$52,774.72	\$158,324
3	Kalamunda Road	Kalamunda Road, HW, (1020001) Road Rehabilitation, Hawkvale Road to Wittenoom Road, SLK 5.90 to 6.99	Mill 40mm Deep, Fill 14 DGA_CRM 75, 40mm Thick	\$660,334.26	\$330,167.13	\$990,501
4	Kalamunda Road	Kalamunda Road, HW, (1020001) Road Rehabilitation, Midland Road to David Street, SLK 4.56 to 4.96	Mill 40mm Deep, Fill 14 DGA_CRM 75, 40mm Thick	\$126,125.93	\$63,062.96	\$189,189

5	Abernethy Road North Bound	Abernethy Road (North Bound), FF, (1020997), Road Rehabilitation, 460m South of Hudswell Road to 330m South of Hudswell Road, SLK 2.25 to 2.38	Mill 40mm Deep Fill, 14 DGA_CRM 75, 40mm Thick	\$51,243.13	\$25,621.57	\$76,865
6	Abernethy Road South Bound	Abernethy Road (South Bound), FF, (1020997), Road Rehabilitation, 170m South of Hudswell Road to 30m North of Hudswell Road, SLK 2.54 to 2.74	Mill 40mm Deep, Fill 14 DGA_CRM 75, 40mm Thick	\$66,130.79	\$33,065.40	\$99,196
<b>Total</b>				<b>\$1,331,727</b>	<b>\$665,863</b>	<b>\$1,997,590</b>