

Roman Road No.	Road Name	Section	SLK	Condition Score	Project Score	Recommended Treatment	Project Cost	MRRG Contribution
1020002	Welshpool Road East (WB)	Lions Walk Lookout to 200 m west of Lesmurdie Road	4.07-4.75	770.1	1479.1	Mill 65 mm, Lay 25 mm thick SMA7-HB, Overlay 40 mm thick 14/75 DGA	\$228,211	\$152,141
1020002	Welshpool Road East (EB)	20 m east of Lions Walk Lookout to 200 m west of Lesmurdie Road	4.04-4.75	733.5	1442.6	Mill 65 mm, Lay 25 mm thick SMA7-HB, Overlay 40 mm thick 14/75 DGA	\$303,249	\$202,166
1020620	Mundaring Weir Road	Weir Carpark to Boundary	15.1-15.82	1605.6	1999.4	Foam Bitumen Stabilise to 150mm, Overlay 40 mm thick 14/75 PMB	\$463,996	\$309,331
102003	Canning Road	Glyde Road to Grove Road	3.14-3.65	706.2	1633.5	Mill 65 mm, Lay 25 mm thick SMA7-HB, Overlay 40 mm thick 14/75 DGA	\$385,874	\$257,249
1020811	Dundas Road	Harrison Road to Carolyn Way	3.13-3.79	934.8	1515.9	Mill 65 mm, Lay 25 mm thick SMA7-HB, Overlay 40 mm thick 14/75 DGA Intersection treatment- Mill 65 mm, Lay 25 mm thick SMA7-HB, Overlay 40 mm thick 14/75 DGA with A15E	\$514,124	\$342,749
1020010	Heath Road	Boonooloo Road to East Terrace	0.38-.67	718.7	1440	Mill 65 mm, Lay 25 mm thick SMA7-HB, Overlay 40 mm thick 14/75 DGA	\$241,998	\$161,332
							\$2,137,452	\$1,424,968